

CAPSULE SUMMARY

F-3-107

Braddock Lutheran Chapel

Frederick vicinity

Private

1907

The Braddock Lutheran Chapel was built in 1907 on the Old National Pike in the village of Braddock about 1/4 mile east of its current site. It was moved to this location in 1974 in order to provide more parking and safer access. The church is a one-story frame hall-type building with a projecting, attached bell tower on the east gable end with a double-doored entrance. The exterior asbestos shingle siding probably covers german siding and the standing seam metal roof may conceal wood shingles. The north and south elevations have Gothic-arched windows and the doorway also has a Gothic arch transom. The new foundation contains a Sunday School in the basement. The open belfry and wood shingled steeple, the projecting bell tower, the overall plan, and the Gothic arched openings are all features common to rural vernacular churches in Frederick County in the period 1880-1920. Although the Braddock Lutheran Chapel has lost considerable integrity by being moved from its original site, these essential elements remain clearly expressed and the building still conveys a feeling of historical time and place.

F-3-107
Braddock Lutheran Chapel
Frederick
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery
Counties, and Baltimore City)

Chronological/Development Period:
Industrial/Urban Dominance, A.D. 1870-1930

Prehistoric/Historic Period Themes
Architecture, Landscape Architecture and Community Planning

Resource Types:

Category: Buildings

Historic Environment: Rural

Historic Function and Use:
Religion/religious structure/church

Known Design Source: None

**Maryland Historical Trust
State Historic Sites Inventory Form****MARYLAND INVENTORY OF
HISTORIC PROPERTIES**

Magi No.

DOE yes x no**1. Name** (indicate preferred name)

historic Braddock Lutheran Chapel

and/or common

2. Locationstreet & number 6938 North Clifton Road not for publicationcity, town Frederick x vicinity of congressional district 6th

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use
<u> </u> district	<u> </u> public	<u> </u> x occupied	<u> </u> agriculture <u> </u> museum
<u> </u> x building(s)	<u> </u> x private	<u> </u> unoccupied	<u> </u> commercial <u> </u> park
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational <u> </u> private residence
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment <u> </u> x religious
<u> </u> object	<u> </u> in process	<u> </u> x yes: restricted	<u> </u> government <u> </u> scientific
	<u> </u> being considered	<u> </u> yes: unrestricted	<u> </u> industrial <u> </u> transportation
	<u> </u> x not applicable	<u> </u> no	<u> </u> military <u> </u> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Braddock Lutheran Chapel

street & number 6938 N. Clifton Road telephone no.:

city, town Frederick state and zip code Md. 21702

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber 936

street & number 100 W. Patrick Street folio 589

city, town Frederick state Md. 21701

6. Representation in Existing Historical Surveys

title

date federal state county local

pository for survey records

city, town state

7. Description

Survey No. F-3-107

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input checked="" type="checkbox"/> moved	date of move <u>1974</u>
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 1

The Braddock Lutheran Chapel is a one-story frame hall-type church with an attached bell tower built in 1907 on the Old National Pike in the village of Braddock about 1/4 mile east of the current location of the building, near Frederick, Frederick County, Maryland. The church was moved to the present location in 1974 to facilitate parking. Its present site is an open field overlooking the interchange of Interstate 70 and U.S. 40A (Old National Pike) to the southwest. Its immediate environment includes several recently built houses and at least one pre-1940 residence in a semi-rural setting. The church faces east and is flanked by a parking lot on the north.

The exterior of the church is covered with asbestos shingle siding, undoubtedly covering or replacing german siding, the most common siding used in the first decades of the 20th century for frame buildings. The new foundation is concrete and includes a basement Sunday School area accessible from the south elevation. The bell tower projects from the east elevation of the church and contains the double-doored entrance. Above the doors is a Gothic-arched transom with textured glass. The belfry of the tower is open with a plain balustrade and a wood shingled steeple topped by a weathervane finial. The main roof is standing seam metal. The main part of the building has three bays on the north and south elevations fill with Gothic-arched windows flanked by louvred shutters. The windows are textureu glass. On the west elevation of the building is a projection which undoubtedly corresponds to a recess behind the altar and pulpit on the interior. At the southwest corner is a modern wood staircase leading from the building's main level to a playground southwest of the church. A concrete block chimney is also located near this corner. At the southeast corner are two inscribed stones, one in brownstone reading "Lutheran Chapel 1907" and the other a modern marble stone reading "Relocated 1974". The interior of the church was inaccessible for this survey.

8. Significance

Survey No.

F-3-107

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400–1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500–1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600–1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700–1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800–1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900–	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1907 **Builder/Architect**

check: Applicable Criteria: ☐ A ☐ B ☒ C ☐ D
and/or
Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☒ local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Braddock Lutheran Chapel is minimally significant for its vernacular architectural style of the early 20th century. The plan, materials, window and door styles, the attached bell tower and open belfry, and the shingled steeple are all characteristic of rural vernacular churches in Frederick County from the 1880's to about 1920. The Braddock Lutheran Chapel was originally built on Old National Pike in the village of Braddock, replacing an earlier union chapel used by the Lutheran and Reformed congregations in the area. Williams and McKinsey's History of Frederick County of 1910 states that a Lutheran congregation was present in the village, called Fair View until about 1890, at least by 1844 when it united with Bethel and Rocky Springs to form a new charge. The 1907 building probably was built when the Reformed Church either closed or merged with another group. The stone building currently used by the Braddock Grange may be the union church which was shared by the two groups. By the 1970's, road traffic on the Old National Pike had increased in volume so much that access and parking to the 1907 church were becoming dangerous. The current site was purchased and the church was moved to the new location in 1974. Although the move decreased the integrity of the Braddock Chapel, it retains as much or more of its exterior appearance as many other rural churches which are in their original locations.

9. Major Bibliographical References

Survey No. F-3-107

Frederick News-Post, Oct. 24, 1974. "Braddock Church Being Moved to New Location"
Land Records of Frederick County
Titus, C.O. Atlas of Frederick County, 1873
Williams, T.J.C., and Folger McKinsey. History of Frederick County, 1910. Reprinted
Baltimore: Regional Publishing Co., 1979, p. 423.

10. Geographical Data

Acreage of nominated property 1 acreQuadrangle name Frederick, Md.Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

Approximately 1 acre centered on the church on Tax Map 66, Parcel 403.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By


name/title Janet L. Davis , Historic Sites Surveyororganization Frederick County Planning & Zoning Dept. date December 1992street & number 12 E. Church Street telephone 696-2958city or town Frederick state Md. 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCE
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2021
JAN 1993



F-3-107

Braddock Lutheran Chapel

Frederick County

C.O. Titus, Atlas of Frederick
County, 1873

Location of earlier church building

Braddock Luth. Ch.

LIBER/PG 10

GRANT

GRANT

F-3-107

936/589
8 Apr 74

Braddock Luth
Church


Crown Oil & Wax
Co. of Delaware

7.42a.

726/591
8 Jul 65

Crown Oil &
Wax Co.

Cloggett B. & Mary
E. Miles



F-3-107
Braddock Lutheran Chapel
Frederick County
USGS Frederick, Md.
1:24000



F. 3-107

Broddack Lutheran Church

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

East elevation

1/2



F-3-107

Broddock Lutheran Church

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Northwest corner view

2/2